3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 150 in cash or Government Promissory Notes, as earnest money and be superscribed, "Tender for restoring Gondichatnahalilkatte Tank, Registered No. 1062 of Shimoga Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with Executive Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance of rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract Estimate of Improving Gondichatnahali tank, Registered No. 1062, Shimoga Taluk.

No.	Items of work	Unit	Quantity
	Bund R. L. 55·00—		
1	Clearing jungle..	L. S Rs.	25
2	Earthwork to bund	Cyds.	11,183
3	Turfing front and rear slopes	Sqres.	1,974
4	Grade stones	Each.	30
5	Bench mark stones	Do	2
6	Tank register No. stone	Do	1
7	Date stone	Do	1
8	Gauge stone	Do	1
9	Cutting grips and filling bund	L. S. Rs.	20
	Sluice No. 1 R. L. 48·00, 24ft. long—		
1	Earthwork	L. S. Rs.	10
2	Brick in surki mortar	Cft.	93
3	Plastering in surki motar	Sqre.	·50
4	Concrete in Surki mortar	Cft.	126
5	Stone-ware pipe including lead	Rft.	28
6	Front orifice slab	Each	1
7	Plug	Each	1
	Sluice No. 2 of Mansonry R. L. 44·50—		
1	Dismantling present work	L. S. Rs.	15
2	Earthwork	Cyds.	180
3	Brick in surki mortar	Cft	792
4	Plastering in surki mortar	Sqres.	3
5	Burnt stone slabs ordinary	Sft.	139
6	Do dressed	Sft.	52
7	Plug with rod complete	L. S. Rs.	8
	Sluice No. 3 of stone-ware pipe R. L. 48·50, 30' long—		
1	Earthwork	Cyds.	14
2	Concrete in surki mortar	Cft.	158
3	Plastering with do	Sqre.	·50
4	Stone ware pipe including lead	Rft.	34
5	Front orifice slab	Each	1
6	Plug	Each	1
	Waste-weir left 35' long at R. L. 50·00—		
1	Earthwork	L. S. Rs.	5
2	Brick in mortar	Cft.	178
3	Burnt stone slabs	Sft.	75
4	Plastering with mortar	Sqre.	1·00
5	Rough stone work	Cyds	8
	Waste-weir 45 feet long, Right R. L. 50·00—		
1	Earthwork	L. S. Rs.	5
2	Brick in mortar	Cft.	203
3	Burnt stone slabs	Sft.	90
4	Plastering in mortar	Sqre.	1·50
5	Rough stone work	Cyds.	8

A. TANDONI RAO,
Executive Engineer.

CHITALDRUG DIVISION.

Dated 13th March 1923.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Chitaldrug Division, up to 30th April 1923, for constructing a Slaughterhouse and

Mutton Stall at Chitaldrug. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1924.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chitaldrug between the hours of 11 A.M. to 5 P.M. on office days.

3. Tenders should be submitted on printed forms, which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items of work specified, will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government promissory notes, as earnest money, and be superscribed "Tender for constructing a Slaughterhouse and Mutton Stall at Chitaldrug," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract of estimate for constructing Slaughterhouse.

No.	Items of work	Per	Quantity
1	Earthwork excavation	100 C. ft.	7·26
2	Do	"	4·15
3	Burnt stone in chunam	"	8·86
4	Burnt brick in chunam	"	15·34
5	Do archwork	"	0·26
6	Burnt stone slabs 6" thick and dressed	S. ft.	1·35
7	Chunam plastering	Sqr.	27·18
8	Whitewashing	"	27·18
9	Cement plastering ½" thick	"	3·00
10	Coping with burnt brick in chunam and plastering over compound wall	R. ft.	45
11	Flooring with granite slabs over 3" concrete and cement pointing	Sqr.	2·19
12	Flooring with Cuddappa slabs on 3" concrete and cement pointed	"	2·36
13	Teakwood pannelled doors with iron fittings	S. ft.	67
14	Do windows with battened shutters, iron bars, etc., complete	"	72
15	Bottom ventilator or airholes with iron bars, etc., complete	"	19
16	Glazed circular ventilators	"	6
17	Teakwood gate with galvanised sheet hinges lock, etc., complete	"	30
18	Bar iron self closing doors	"	72
19	Teakwood work wrought and put up including wood oiling	C. ft.	51·79
20	Teakwood eave boards	R. ft.	209
21	Roofing with 1st class Mangalore tiles on teak reepers, etc., complete	Sqr.	8·26
22	Cement concrete drains	R. ft.	58
23	Well for depositing water	Lump sum	
24	Leather hose, etc.	"	
25	Hand pump for raising water	"	
26	One cart for receiving gut contents	"	
27	Iron hooks for airing and skinning rooms	"	
28	Cement pointing	Sqr.	95
29	Zinc sheet for valley	S. ft.	15
30	Ridge tiles set in mortar	R. ft.	57
31	Painting to doors and windows and chunam border to the end of gables, etc.	Lump sum	
32	Rolled steel beams of British sections to support iron tanks	"	
33	Iron tank	No.	1
34	Finials over-roof	"	5
35	Water pipe connections	Lump sum	

Abstract estimate for constructing Mutton Stall.

1	Earthwork excavation	100 C. ft.	1·83
2	Burnt stone slabs 6" thick, roughly dressed	S. ft.	161
3	Burnt brick in mortar	100 C. ft.	2·01
4	Filling in the basement with good gravel and tamping and watering, etc.	"	0·76
5	Teakwood wrought and put up	C. ft.	43·06
6	Roofing with 1st class Mangalore tiles on teak reepers, etc.	Sqr.	5·28
7	Flooring with 4½" thick burnt stone slabs including cement pointing	"	3·00
8	Sundry charges, etc.	Lump sum	

S. A. RAMASWAMI IYER,
Executive Engineer.